

Adopting MiC (Modular Integrated Construction)

採用MiC建築法

采用MiC建筑法

- *In situ* construction waste was drastically reduced since the fabrication of MiC Units was performed in factory.
- MiC組件於工廠內製造，大大減少工地現場所要處理的廢料。
- MiC組件于工厂内制造，大大减少工地现场所要处理的废料。



Adopting MiC (Modular Integrated Construction)

採用MiC建築法

采用MiC建筑法

- The noise level was much lower than conventional construction methods.
- 較傳統建築方法噪音低，滋擾亦較少。
- 较传统建筑方法噪音低，滋扰亦较少。



Mitigation measures for air pollution

空氣污染緩解措施

空气污染缓解措施

- Adopting water truck for cleaning up haul road and dust suppression.
- 採用水車行走工地各處，清理路面及降塵。
- 採用水車行走工地各處，清理路面及降塵。



Mitigation measures for air pollution

空氣污染緩解措施

空气污染缓解措施

- Install sprinkler and arrange labourers to spray water for the unreachable area.
- 安裝花灑頭及人手灑水，以彌補水車未能到達的地方。
- 安装花洒头及人手洒水，以弥补水车未能到达的地方



Noise control

減少噪音滋擾

減少噪音滋擾

- As night works was needed, we obtained the permit from EPD. In order to minimize the nuisance, silenced-type equipment and noise barrier were adopted.
- 因需晚上施工，預早向環保署申請有關許可證，並採用低噪音型機械，及安裝隔音裝置，減少滋擾。
- 因需晚上施工，預早向環保署申請有关许可证，并采用低噪音型机械，及安装隔音装置，减少滋扰。



Water Treatment

污水處理

污水处理

- Made use of Water Treatment Plant to treat all the wastewater from the project site.
- 採用大型污水處理機，收集工地所有的污水集中處理，合乎標準才排放。
- 采用大型污水处理机，收集工地所有的污水集中处理，合乎标准才排放。

